CLAIM NO.: 210401AB-001

Date of Loss:
Carrier: Insurance Company
Deductible: $0.00

INSURED

Mario Hosea (Jump.org, LLC)
10605 Prince Ave Cleveland OH 44105-2755

Loss address:
10605 Prince Ave Cleveland OH 44105-2755

Adjuster: Abe Kruse
Phone: 216-777-7154

This estimate is subject to review and may be supplemented, modified, or revised by the insurance company or its assigned adjuster based on coverage determinations, policy conditions, and claim evaluation.

#	Description	Quantity	Unit Price	Per	Total O&P	Total Taxes	RC	Depreciation	ACV
ESTIMATE: Structure								Claim #210401AB-001, Mario Hosea (Jump.org, LLC)	
In progress									
ROOFPLAN: Estimate from Estimate 210401AB.pdf — 10605 Prince Ave Cleveland OH 44105-2755									
SHINGLES									
1	Shingles, Composition, Laminated/Architectural, Good - Tear Out	7.16	64.14	SQ	$0.00	$0.00	$459.24	$0.00	$459.24
2	Shingles, Composition, Laminated/Architectural, Good - Replace	7.52	278.18	SQ	$0.00	$0.00	$2,170.62	$0.00	$2,170.62
3	Shingles, Starter Row, Eave, Continuous - Replace	39.64	2.14	LF	$0.00	$0.00	$86.63	$0.00	$86.63
4	Ridge Cap Shingles, 3-Tab - Remove	11.46	2.10	LF	$0.00	$0.00	$24.07	$0.00	$24.07
5	Ridge Cap Shingles, 3-Tab - Replace	36.86	5.01	LF	$0.00	$0.00	$188.00	$0.00	$188.00
6	Steep Roof Charge, Asphalt Shingle Roof, 10/12-12/12 - Tear Out	7.16	20.20	SQ	$0.00	$0.00	$144.63	$0.00	$144.63
7	Steep Roof Charge, Asphalt Shingle Roof, 10/12-12/12 - Replace	7.16	51.60	SQ	$0.00	$0.00	$369.46	$0.00	$369.46
8	Drip Edge, Eave/Rake, Aluminum, Pre-Finished Color - Tear Out	75.88	0.56	LF	$0.00	$0.00	$42.49	$0.00	$42.49
9	Drip Edge, Eave/Rake, Aluminum, Pre-Finished Color - Replace	79.67	2.96	LF	$0.00	$0.00	$246.66	$0.00	$246.66
	SHINGLES - Subtotal (9 items)				**$0.00**	**$0.00**	**$3,731.80**	**$0.00**	**$3,731.80**
UNDERLAYMENTS									
10	Felt, Single Layer, 15 lb. - Replace	6.27	35.60	SQ	$0.00	$0.00	$227.34	$0.00	$227.34
	UNDERLAYMENTS - Subtotal (1 item)				**$0.00**	**$0.00**	**$227.34**	**$0.00**	**$227.34**
VENTS AND FLASHINGS									
11	Flashing, Chimney, Galvanized, Small - Tear Out	1.00	25.73	EA	$0.00	$0.00	$25.73	$0.00	$25.73
12	Flashing, Chimney, Galvanized, Small - Replace	1.00	277.68	EA	$0.00	$0.00	$282.76	$0.00	$282.76
13	Flashing, Pipe Jack, Plastic - Tear Out	1.00	12.43	EA	$0.00	$0.00	$12.43	$0.00	$12.43
14	Flashing, Pipe Jack, Plastic - Replace	1.00	33.22	EA	$0.00	$0.00	$33.92	$0.00	$33.92
	VENTS AND FLASHINGS - Subtotal (4 items)				**$0.00**	**$0.00**	**$354.84**	**$0.00**	**$354.84**
DEBRIS REMOVAL									
15	Dumpster, 5 Yard	1.00	399.72	EA	$0.00	$0.00	$431.70	$0.00	$431.70
	DEBRIS REMOVAL - Subtotal (1 item)				**$0.00**	**$0.00**	**$431.70**	**$0.00**	**$431.70**
GENERAL									
16	Roof & Wall Tarping, 151-250 SF	1.00	324.02	EA	$0.00	$0.00	$349.94	$0.00	$349.94
17	Height Allowance, Roof Covering, 2 Story - Tear Out	7.16	13.39	SQ	$0.00	$0.00	$95.87	$0.00	$95.87
18	Height Allowance, Roof Covering, 2 Story - Replace	7.16	17.52	SQ	$0.00	$0.00	$125.44	$0.00	$125.44
19	Ice/Water Shield, Single Row, LF - Tear Out	39.64	0.40	LF	$0.00	$0.00	$15.86	$0.00	$15.86
20	Ice/Water Shield, Single Row, LF - Replace	41.62	3.64	LF	$0.00	$0.00	$156.62	$0.00	$156.62
	GENERAL - Subtotal (5 items)				**$0.00**	**$0.00**	**$743.73**	**$0.00**	**$743.73**

ESTIMATE: Structure | Claim #210401AB-001, Mario Hosea (Jump.org, LLC)

In progress

CATEGORY SUMMARY

Category	Items	RC	Depreciation	ACV
SHINGLES	9	$3,731.80	$0.00	$3,731.80
UNDERLAYMENTS	1	$227.34	$0.00	$227.34
VENTS AND FLASHINGS	4	$354.84	$0.00	$354.84
DEBRIS REMOVAL	1	$431.70	$0.00	$431.70
GENERAL	5	$743.73	$0.00	$743.73
Total		**$5,489.41**	**$0.00**	**$5,489.41**

ESTIMATE SUMMARY

Estimate Name	Subtotal
Structure (YICN Roofing)	$5,489.41

CLAIM TOTALS

Total taxes:	$0.00
Total RCV:	$5,489.41
Actual Cash Value:	**$5,489.41**
Deductible:	($0.00)
Net ACV:	**$5,489.41**

COVERAGE SUMMARY

Coverage	RC	Depreciation	Applied Deductible	Net ACV	Payable if Recovered
Building	$5,489.41	$0.00	$0.00	$5,489.41	$0.00
Totals	**$5,489.41**	**$0.00**	**$0.00**	**$5,489.41**	**$0.00**