
CLAIM NO.: 210401AB-001	Reinspection ☐	**INSURED**
Policy No.:	105409560	Mario Hosea (Jump.org, LLC) 1468 West 9th St Ste 100 Cleveland OH 44113-1252
Date of Loss:	07/18/2026 1:37 AM	Home phone: Business phone: Mobile phone: Bus. Fax: Contact:
Type of Loss:	Weather - Wind	**Loss address:** 10605 Prince Ave Cleveland OH 44105-2755
Deductible:	$2,500.00	
Year Built:	1929 **Cat No.:** 05626	
Adjuster:	Abe Kruse	
License Number:		
Phone:	(513) 947-5331	
Fax Number:		
Email Address	akruse@amig.com	

As a result of your claim, the Company may conduct a future inspection of your property to confirm the claimed damages have been repaired. It is expected that proceeds from this claim payment will be used to repair your property to the pre-loss condition. If repairs are not properly completed at the time of the inspection, the Company may elect to discontinue the insurance at the next renewal date following the inspection. This estimate is subject to review and may be supplemented, modified, or revised by the Company or its assigned claim adjuster based on coverage determinations, policy conditions, and claim evaluation.

Description	Quantity	Unit Price	Per	Age/Life	Condition	Total O&P	Total Taxes	RC	Depreciation	ACV
ESTIMATE: Structure								Claim #210401AB-001, Mario Hosea (Jump.org, LLC)		
In progress										
ROOFPLAN: Roofplan Dwelling										
General Items										
1 Roof & Wall Tarping, 151-250 SF	1	$324.02	EA			$0.00	$25.92	$349.94	$0.00	$349.94
Tax override applied - Sales Tax applied to materials, labor, equipment.										
2 Dumpster, 5 Yard	1	$399.72	EA			$0.00	$31.98	$431.70	$0.00	$431.70
Tax override applied - Sales Tax applied to materials, labor, equipment.										
General Items - Subtotal *(2 items)*						**$0.00**	**$57.90**	**$781.64**	**$0.00**	**$781.64**
Roof										
Roof area: 1,922.08 SF **Squares:** 19.2 SQ **Soffit:** 343.81 SF										
Eaves: 133.04 LF **Ridge:** 45.93 LF										
SHINGLES										
3 Shingles, Composition, Laminated/Architectural, Good - Tear Out	7.16	$64.14	SQ	0/30	Average	$0.00	$0.00	$459.24	$0.00	$459.24
4 Shingles, Composition, Laminated/Architectural, Good - Replace	7.52	$278.18	SQ	0/30	Average	$0.00	$78.70	$2,170.62	$0.00	$2,170.62
Includes 5% waste on quantity.										
Top left slope only that had wind damages										
5 Shingles, Starter Row, Eave, Continuous - Replace	39.64	$2.14	LF	0/20	Average	$0.00	$1.81	$86.63	$0.00	$86.63
This item has been applied to the eaves of the roof.										
6 Ridge Cap Shingles, 3-Tab - Remove	11.46	$2.10	LF			$0.00	$0.00	$24.07	$0.00	$24.07
7 Ridge Cap Shingles, 3-Tab - Replace	36.86	$5.01	LF	0/20	Average	$0.00	$3.33	$188.00	$0.00	$188.00
8 Height Allowance, Roof Covering, 2 Story - Tear Out	7.16	$13.39	SQ	0/0	Average	$0.00	$0.00	$95.87	$0.00	$95.87
9 Height Allowance, Roof Covering, 2 Story - Replace	7.16	$17.52	SQ	0/0	Average	$0.00	$0.00	$125.44	$0.00	$125.44



Description	Quantity	Unit Price	Per	Age/Life	Condition	Total O&P	Total Taxes	RC	Depreciation	ACV
ESTIMATE: Structure								Claim #210401AB-001, Mario Hosea (Jump.org, LLC)		
In progress										
10 Steep Roof Charge, Asphalt Shingle Roof, 10/12-12/12 - Tear Out	7.16	$20.20	SQ	0/0	Average	$0.00	$0.00	$144.63	$0.00	$144.63
11 Steep Roof Charge, Asphalt Shingle Roof, 10/12-12/12 - Replace	7.16	$51.60	SQ	0/0	Average	$0.00	$0.00	$369.46	$0.00	$369.46
UNDERLAYMENTS										
12 Felt, Single Layer, 15 lb. - Replace	6.27	$35.60	SQ	0/20	Average	$0.00	$4.13	$227.34	$0.00	$227.34
Includes 5% waste on quantity.										
13 Ice/Water Shield, Single Row, LF - Tear Out	39.64	$0.40	LF	0/25	Average	$0.00	$0.00	$15.86	$0.00	$15.86
Conversion: 0.03 SQ per LF										
14 Ice/Water Shield, Single Row, LF - Replace	41.62	$3.64	LF	0/25	Average	$0.00	$5.13	$156.62	$0.00	$156.62
Includes 5% waste on quantity.										
Conversion: 0.03 SQ per LF										
15 The quantity of felt has been reduced by the amount of ice and water shield used.										
VENTS AND FLASHINGS										
16 Drip Edge, Eave/Rake, Aluminum, Pre-Finished Color - Tear Out	75.88	$0.56	LF	0/20	Average	$0.00	$0.00	$42.49	$0.00	$42.49
17 Drip Edge, Eave/Rake, Aluminum, Pre-Finished Color - Replace	79.67	$2.96	LF	0/20	Average	$0.00	$10.84	$246.66	$0.00	$246.66
Includes 5% waste on quantity.										
18 Flashing, Chimney, Galvanized, Small - Tear Out	1	$25.73	EA	0/25	Average	$0.00	$0.00	$25.73	$0.00	$25.73
19 Flashing, Chimney, Galvanized, Small - Replace	1	$277.68	EA	0/25	Average	$0.00	$5.08	$282.76	$0.00	$282.76
20 Flashing, Pipe Jack, Plastic - Tear Out	1	$12.43	EA	0/25	Average	$0.00	$0.00	$12.43	$0.00	$12.43
21 Flashing, Pipe Jack, Plastic - Replace	1	$33.22	EA	0/25	Average	$0.00	$0.70	$33.92	$0.00	$33.92
Roof - Subtotal *(22 items)*						**$0.00**	**$109.72**	**$4,707.77**	**$0.00**	**$4,707.77**
Roofplan Dwelling - Subtotal *(24 items)*						**$0.00**	**$167.62**	**$5,489.41**	**$0.00**	**$5,489.41**

ESTIMATE: Structure	Claim #210401AB-001, Mario Hosea (Jump.org, LLC)
In progress	
Total Materials:	$1,875.26
Total Labor:	$3,446.53
Subtotal:	**$5,321.79**
Sales Tax 8.000% (applies to materials only, some items overridden):	$167.62
Replacement Cost Value:	**$5,489.41**
Net Actual Cash Value Estimate:	**$5,489.41**
Deductible ($2,500.00):	$(2,500.00)
Net Estimate:	**$2,989.41**
Net Estimate:	**$2,989.41**

Finalization