ROOF ESTIMATE

ROOF REPORT

DRAFT

April 11, 2026

A

PREPARED FOR

—


12819 Hoy Avenue, Cleveland, OH 44105

PREPARED BY

—

Estimate Date: April 11, 2026

Property Image



12819 Hoy Avenue, Cleveland, OH 44105 — Satellite imagery

Roof Summary

ROOF AREA	ORDER QUANTITY	PITCH	CONFIDENCE
11.4	**12.6**	**10/12**	A
SQ (1,142.5 sq ft)	SQ (+10% waste)	—	88%

Linear Measurements

DRAFT

12819 Hoy Avenue, Cleveland, OH 44105

MEASUREMENT	LENGTH	CONFIDENCE
Ridge	**34.0 LF**	82%
Hip	**5.0 LF**	85%
Valley	**21.0 LF**	78%
Rake	**64.0 LF**	82%
Eave	**75.0 LF**	82%
Step Flashing	**15.0 LF**	75%

Waste Calculation — 1,142.5 sq ft base

Waste %	5%	10%	12%	15%	17%	20%
Area (sq ft)	1,200	**1,257**	1,280	1,314	1,337	1,371
Squares	12.0	**12.6**	12.8	13.1	13.4	13.7

5 segments detected. Area method: segment_sum.

Estimate Details

DRAFT

12819 Hoy Avenue, Cleveland, OH 44105

CODE	DESCRIPTION	QTY	UNIT	RATE	RCV	ACV
3_TAB__25_YR	3 tab - 25 yr. - comp. shingle roofing	12.79	SQ	$273.00	$3491.67	$3491.67
ROOFING_FELT__15_LB	Roofing felt - 15 lb.	12.79	SQ	$41.18	$526.69	$526.69
ICE__WATER_BARRIER	Ice & water barrier	329.28	SF	$2.02	$665.15	$665.15
ASPHALT_STARTER__UNI	Asphalt starter - universal starter course	155.68	LF	$2.18	$339.38	$339.38
RR_DRIP_EDGE	R&R Drip edge	155.68	LF	$3.16	$491.95	$491.95
RR_RIDGE_CAP__VENTIN	R&R Ridge cap - venting ridge cap shingles	38.08	LF	$12.59	$479.43	$479.43
RR_RIDGE_CAP__VENTIN	R&R Ridge cap - venting ridge cap shingles	5.60	LF	$12.59	$70.50	$70.50
RR_VALLEY_W_FLASHING	R&R Valley "W" flashing for metal roofing	23.52	LF	$9.75	$229.32	$229.32
RR_FLASHING_14_WIDE	R&R Flashing, 14" wide	16.80	LF	$5.52	$92.74	$92.74
REMOVE_3_TAB__25_YR_	Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	12.79	SQ	$76.31	$976.00	$976.00
RR_FLASHING__PIPE_JA	R&R Flashing - pipe jack	2	EA	$59.37	$118.74	$118.74
RR_ROOF_VENT__TURTLE	R&R Roof vent - turtle type - Metal	2	EA	$79.44	$158.88	$158.88
REMOVE_ADDITIONAL_CH	Remove Additional charge for steep roof	11.42	SQ	$19.00	$216.98	$216.98

CODE	DESCRIPTION	QTY	UNIT	RATE	RCV	ACV
	- 7/12 to 9/12 slope					
RR_ADD_CHARGE_FOR_SH	R&R Add charge for sheathing steep roof - 7/12 - 9 /12 slope	11.42	SF	$0.28	$3.20	$3.20
REMOVE_ADDITIONAL_CH	Remove Additional charge for high roof (2 stories or greater)	11.42	SQ	$7.17	$81.88	$81.88
1491_RR_OUTLET__HIGH	1,491. R&R Outlet - High grade	11.42	EA	$21.54	$245.99	$245.99
				Total RCV:	**$8188.50**	**$8188.50**

CompanySync • Generated April 11, 2026 • This estimate is valid for 30 days from the date shown.