ROOF ESTIMATE

ROOF REPORT

DRAFT

June 1, 2026

A

PREPARED FOR

—

5420 Mardale Avenue, Bedford Heights, OH 44146

PREPARED BY

—

Estimate Date: June 1, 2026

Property Image



5420 Mardale Avenue, Bedford Heights, OH 44146 — Satellite imagery

Roof Summary

ROOF AREA	ORDER QUANTITY	PITCH	CONFIDENCE
29.4	**32.3**	**4/12**	A
SQ (2,937.264 sq ft)	SQ (+10% waste)	—	88%

Linear Measurements

DRAFT

5420 Mardale Avenue, Bedford Heights, OH 44146

MEASUREMENT	LENGTH	CONFIDENCE
Ridge	**54.0 LF**	82%
Hip	**8.0 LF**	85%
Valley	**34.0 LF**	78%
Rake	**102.0 LF**	82%
Eave	**120.0 LF**	82%
Step Flashing	**24.0 LF**	75%

Waste Calculation — 2,937.264 sq ft base

Waste %	5%	10%	12%	15%	17%	20%
Area (sq ft)	3,084	**3,231**	3,290	3,378	3,437	3,525
Squares	30.8	**32.3**	32.9	33.8	34.4	35.3

5 segments detected. Area method: segment_sum.

CompanySync • Generated June 1, 2026

Estimate Details

DRAFT

5420 Mardale Avenue, Bedford Heights, OH 44146

CODE	DESCRIPTION	QTY	UNIT	RATE	RCV	ACV
LAMINATED_COMP_SH	Laminate - comp. shingle roofing - per SQ	32.89	SQ	$273.00	$8978.97	$8978.97
ROOFING_FELT	Roofing felt - synthetic underlayment - Standard grade	32.89	SQ	$45.48	$1495.84	$1495.84
ICE__WATER_B	Ice & water barrier	527.52	SF	$2.02	$1065.59	$1065.59
ASPHALT_STAR	Asphalt starter - universal starter course	248.64	LF	$2.18	$542.04	$542.04
RR_DRIP_EDGE	R&R Drip edge	248.64	LF	$3.16	$785.70	$785.70
RR_RIDGE_CAP	R&R Ridge cap - venting ridge cap shingles	60.48	LF	$12.59	$761.44	$761.44
RR_RIDGE_CAP	R&R Ridge cap - venting ridge cap shingles	8.96	LF	$12.59	$112.81	$112.81
RR_VALLEY_W	R&R Valley "W" flashing	38.08	LF	$7.12	$271.13	$271.13
RR_FLASHING_14	R&R Flashing, 14" wide	26.88	LF	$5.52	$148.38	$148.38
REMOVE_3_TAB	Remove 3 tab - 25 yr. - comp. shingle roofing	32.89	SQ	$76.31	$2509.84	$2509.84
RR_FLASHING_PIPE_JACK	R&R Flashing - pipe jack	1	EA	$59.37	$59.37	$59.37
RR_ROOF_VENT_TURTLE	R&R Roof vent - turtle type - Plastic	2	EA	$69.14	$138.28	$138.28

CODE	DESCRIPTION	QTY	UNIT	RATE	RCV	ACV
				Total RCV:	**$16869.38**	**$16869.38**

CompanySync • Generated June 1, 2026 • This estimate is valid for 30 days from the date shown.