YICN Roofing (aka Your Insurance Claims Network)
675 Alpha Dr
Highland Heights, OH 44143
937-756-2124
yicnroofing.com

ESTIMATE

Date: 9/26/2026
Estimate #: EST-2026-5550

PREPARED FOR

kevin stone

5420 Mardale Ave, Bedford Heights, OH 44146, USA

2165103240
stonekevin866@gmail.com

Roof Analysis Summary

Roof Area:	2,937 sq ft	**Complexity:**	MODERATE
Roofing Squares:	30 squares	**Waste Factor:**	10%
Roof Type:	Gable	**Adjusted Squares:**	33.0 squares
		AI Confidence:	95%

Materials List

ITEM	QTY	UNIT	NOTES
Architectural Shingles	33	Squares	99 bundles (3 per sq)
Shingle Bundles	99	Bundles	Waste: 10%
Synthetic Underlayment	4	Rolls	Covers 4000 sq ft
Starter Strip Shingles	3	Bundles	228 LF coverage
Ridge Cap Shingles	2	Bundles	44 LF (30 LF/bundle)
Roofing Nails (1¼")	2	Boxes	14,400 nails total
Ridge Cap Nails	1	Boxes	For ridge cap installation
Drip Edge (10ft)	23	Pieces	Total: 228 LF
Ice & Water Barrier	4	Rolls	228 LF coverage
Ridge Vent	11	Pieces	4 LF per piece

Soffit Intake Vents	10	Pieces	Under eave ventilation
Metal Valley Flashing	1	Pieces	9 LF (10 LF/piece)
Step Flashing (10ft)	1	Pieces	Wall/chimney flashing
Step Flashing (8ft)	1	Pieces	Wall/chimney flashing

Material Summary

Area: 2,937 sq ft (30 squares) • Adjusted with 10% waste: 33.0 squares

Cost Estimate

$16,154

Recommendations

Professional on-site inspection recommended for final quote

- Consider architectural shingles for Ohio weather
- Ensure proper ventilation during installation

Terms & Conditions

A 5-year workmanship, no defect warranty, backs all work. If for any reason, the property experiences any leakage around the area that was repaired or replaced, we will gladly fix the problem at no charge to the company.

NOTE: This price is only valid until October 26, 2026, and is based on a deposit of half down upon acceptance of the estimate and the remaining half due upon completion of work.

In addition, we will replace up to 3 sheets of 1/2 OSB sheathing at no cost. Additional sheets to be installed will be at $65.00 per sheet.

Call 937-756-2124 to schedule your FREE inspection

YICN Roofing (aka Your Insurance Claims Network)

675 Alpha Dr, Highland Heights, OH 44143

937-756-2124 • yicnroofing.com