YICN Roofing
216-777-7154
yicnteam@gmail.com
675 Alpha Dr

ESTIMATE

EST-1881 (AI)
August 4, 2026

PREPARED FOR

SAKINAH DAVIS
2167892114
6239 WHITETAIL RUN , Oakwood Village, OH, 44146

PREPARED BY

YICN Roofing
Date: 8/4/2026
216-777-7154
yicnteam@gmail.com
Claim #: JFM1154001H

#	Description	Qty	Unit	Rate	RCV	ACV
1	Tear off, haul and dispose of comp. shingles - 3 tab	22.43	SQ	$69.42	$1557.09	$1557.09
2	Roofing felt - 15 lb.	17.17	SQ	$39.84	$684.05	$171.01
3	*(Unlabeled item)*	25.33	SQ	$260.73	$6604.29	$2641.72
4	Continuous ridge vent - shingle-over style	58.93	LF	$11.20	$660.02	$377.13
5	Flashing - pipe jack	1	EA	$58.47	$58.47	$33.41
6	R&R Gutters - aluminum - up to 5"*	127	LF	$10.95	$1390.65	$556.26
7	Remove Gable cornice return - 3 tab	1	EA	$15.17	$15.17	$15.17
8	Install Gable cornice return - 3 tab	1	EA	$88.50	$88.50	$35.40
9	Remove Additional charge for high roof (2 stories or greater)	16.09	SQ	$6.41	$103.14	$103.14
10	Additional charge for high roof (2 stories or greater)	16.09	SQ	$24.58	$395.49	$98.87

11	Remove Additional charge for steep roof - 10/12 - 12/12 slope	5.80	SQ	$24.71	$143.32	$143.32
12	Additional charge for steep roof - 10/12 - 12/12 slope	5.80	SQ	$81.19	$470.90	$117.73
13	Drip edge	0	LF	$0.00	$0.00	$0.00
14	Ice & water barrier for heated eaves*	0	SF	$0.00	$0.00	$0.00
15	Roofing felt - 15 lb.	4.36	SQ	$39.84	$173.70	$43.43
16	Roll roofing - w/out felt	0	SQ	$0.00	$0.00	$0.00
17	Roofing felt - 15 lb.	0.90	SQ	$39.84	$35.86	$8.96
18	R&R Window screen, 1 - 9 SF	9	EA	$48.53	$436.77	$436.77
19	R&R Shutters - simulated wood (polystyrene)	3	EA	$182.34	$547.02	$273.51
20	R&R Clothes dryer vent cover	1	EA	$43.27	$43.27	$43.27
21	R&R Exterior light fixture	1	EA	$110.40	$110.40	$110.40
22	R&R Exterior light fixture for exterior light post*	1	EA	$110.40	$110.40	$110.40
23	R&R Rural mailbox	1	EA	$63.73	$63.73	$63.73
24	R&R Fascia - metal - 6"	36.25	LF	$7.56	$274.05	$191.84
25	R&R Downspout - aluminum - up to 5"*	22.50	LF	$10.95	$246.37	$98.55
26	R&R Siding - vinyl	62	SF	$6.44	$399.28	$279.50

27	R&R Downspout - aluminum - up to 5"*					
		10.50	LF	$10.95	$114.97	$45.99
28	R&R Fascia - metal - 6"					
		9.50	LF	$7.56	$71.82	$50.27
29	R&R Imperial 4 in. x 4 in. Outdoor Black Cast Aluminum LED Solar Post Cap (2-Pack)*					
		4	EA	$40.26	$161.04	$161.04
30	R&R Window screen, 1 - 9 SF					
		2	EA	$48.53	$97.06	$97.06
31	Reglaze window, 1 - 9 sf					
		1	EA	$84.65	$84.65	$84.65
32	Comb and straighten a/c condenser fins - with trip charge					
		1	EA	$201.41	$201.41	$201.41
33	Patio door screen - rescreen, 17 - 25 SF*					
		1	EA	$62.99	$62.99	$62.99
34	R&R Siding - vinyl					
		615	SF	$6.44	$3960.60	$2772.42
35	House wrap (air/moisture barrier)					
		0	SF	$0.00	$0.00	$0.00
36	R&R Fascia - metal - 6"					
		31.67	LF	$7.56	$239.43	$167.60
37	R&R Downspout - aluminum - up to 5"*					
		42.75	LF	$10.95	$468.11	$187.25
38	Remove Direct vent termination cap - galvanized					
		1	EA	$91.04	$91.04	$91.04
39	Install Direct vent termination cap - galvanized					
		1	EA	$78.31	$78.31	$78.31
40	Low voltage box - Detach & reset					
		1	EA	$47.05	$47.05	$47.05
41	Heater - Patio					
		1	EA	$220.00	$220.00	$220.00
42	Tandem axle dump trailer - per load - including dump fees					
		1	EA	$292.61	$292.61	$292.61

43	Window labor minimum	1	EA	$61.09	$61.09	$61.09
44	Electrical labor minimum	1	EA	$107.58	$107.58	$107.58
45	Tax	1	EA	$577.25	$577.25	$577.25

SUBTOTAL:	**$21548.96**
Adjustment:	$-11478.96
TOTAL (RCV):	**$10070.00**
Less Depreciation:	-$8732.75
Actual Cash Value (ACV):	**$12816.20**

NOTE:

This price is only valid for 30 days from estimate date, and is based on a deposit of half down upon acceptance of estimate and the remaining half due upon completion of work.

The estimate is hereby based on seen, disclosed, or otherwise obvious damage. The repair of the covered loss may be higher than these figures because of other circumstances not yet discovered. Included in this estimate are the items that the Contractor believes necessary to return the property to pre loss condition.

Unseen, undisclosed, or otherwise not obvious conditions, if discovered later or during the course of repairs, will be considered not included.

If discovered, any necessary additional repairs will be submitted for supplemental coverage, based on current market pricing.

Terms & Conditions:

The following estimate is only an approximation of the damages suffered, or expenses incurred, by the insured. No warranty or representation with regard to the accuracy of the estimate is expressed or implied and none should be inferred. The actual damages suffered, or expenses incurred, could be higher or lower than the estimate, even significantly, depending on variances in a number of factors affecting the estimate and the accuracy of the information and assumptions upon which the estimate is based.

Warranty & Additional Terms:

1. Coverage Period
YICN Roofing (the "Contractor") warrants to the original Property Owner that the roofing system installed will be free from defects in workmanship for a period of ten (10) years from the date of substantial completion.

2. Scope of Warranty
This warranty covers leaks or structural failures directly resulting from errors in the installation process, including:

Improper fastening of shingles or underlayment.

Incorrect installation of flashing (chimneys, valleys, pipe boots).

Failure to adhere to manufacturer-specified installation patterns.

3. Remedy
If a workmanship defect is identified during the 10-year period, the Contractor will provide the labor and materials necessary to repair the specific affected area at no cost to the Property Owner.

4. Exclusions
This warranty specifically excludes damage caused by:

Acts of God: Hail, winds exceeding manufacturer ratings, lightning, or fallen trees.

Existing Structures: Movement or settling of the building's foundation or roof deck.

Third-Party Alterations: Modifications made by other contractors (e.g., satellite dish installation, solar panels, or gutter repairs).

Lack of Maintenance: Failure by the owner to keep the roof free of debris or ice dams.

Material Defects: Failures in the shingles or products themselves (which are covered by the Manufacturer’s Warranty).

5. Transferability
This warranty is non-transferable unless otherwise agreed upon in writing at the time of title transfer. A one-time transfer may be permitted within the first two (2) years of the warranty period, subject to a professional inspection by the Contractor.

6. Claim Procedure
To report a claim, the Property Owner must notify the Contractor within 48 hours of discovering the leak or defect. Failure to provide timely notice that results in additional interior damage may void the labor coverage for those consequential damages.

Production Manager

675 Alpha Dr
Highland Heights, OH 44143

Thank you for your business!